# Domestic driveway ice and snow melting system

# HEATCOM SMART HEATING SOLUTIONS





### The Goal

Heatcom specified a driveway heating system to provide safe access to a property in Dobcross near Oldham, Greater Manchester.

The driveway of the house is incredibly steep and poses a serious danger in winter when the owner's car often slides on ice down to the main road below.

The drive leads directly onto the A62, a busy yet narrow road into Huddersfield from the Saddleworth village.

Contractor Springwood Construction was commissioned to install a Heat Mat driveway heating system to melt ice and snow where the tyres meet the ground.



#### **About Heatcom**

At Heatcom, we are specialists in electric heating solutions for indoor and outdoor environments.

Founded in Denmark, we deliver high-quality, energy-efficient, and easyt-to-install systems to customers around the world. Our product range includes underfloor heating, ice and snow melting

# Heatcom's Solution via Heat Mat

To enable safe access and prevent the owner's vehicle losing grip, two tyre tracks at the edges of the driveway were fitted with exterior heating cable to heat the only access route in snow or icy conditions.

Heatcom specified a 7mm exterior cable accompanied by a ground moisture senor and 47Amp thermostat for temperature control.

The cable was attached to reinforced construction mesh using robust cable ties, before being covered with sand. The driveway was finished with decorative paving blocks. Fully automated control systems are supplied that can

# **The Result**

The owner has spent many years struggling to get out of the drive in snow or risking his safety in icy conditions. "I've had a few hairy moments with black ice and been stuck in the drive on numerous occasions" says the owner.

The system will provide peace of mind and enable safe access to the property when dangerous snow or ice is present.

# **Project in detail**

## **Date Installed**

2014

#### Location

Dobcross, Greater, Manchester, UK

#### Client

Home owner

#### System supplied through

North-East based distributor

#### Installer

Springwood Construction

# **System specifications:**

- 7mm ice and snow melting cable fitted onto reinforced construction mesh
- · 47Amp thermostat
- · Ground moisture sensor

The system ensures the drive is free from dangerous ice in winter...

Heatcom Corporation A/S
Barmstedt Allé 6
5500 Middelfart
Tel. +45 63 41 77 77
Sales@Heatcom dk

